

CONSTRUCTION CHEMICALS

CERAMIC TILE
ADHESIVES
& GROUTS

Dribond

WATERPROOFING PRODUCTS
FOR CONCRETE AND MASONRY

WEB SITE

www.constructionchemicals.com.au

Adelaide
135 Cormack Rd
Wingfield S.A. 5013
Ph: (08) 82437888
Fax: (08) 82437800
Email
conchem@ozemail.com.au

ABN 66 008 091 503

Brisbane
45 Coulson Street
Wacol Qld 4076
Ph (07) 32712944
Fax (07) 32713892
Email
conchem.qld@bigpond.com.au

Melbourne
11 Gabrielle Court
Bayswater North Vic 3153
Ph (03) 97614711
Fax (03) 97614748

Perth
11 Collie Road
Welshpool W.A. 6106
Ph (08) 93569999
Fax (08) 93569955

Sydney
2 / 31-33 Newton Road
Wetherill Park N.S.W. 2164
Ph (02) 97563533
Fax (02) 97563534

Auckland
16 Carpenter Road
East Tamaki N.Z.
Ph (09) 2735444
Fax 0800266236

Kuala Lumpur
Lot 2 Jalan Kecepi,
33/2 Elite Industrial Estate
Off Jalan Bukit Kemuning
40000 Shah Alam
Ph (603) 51222522
Fax (603) 51222526

Project Name:

Contact:

Construction Chemicals WATERPROOFING SPECIFICATION

2. WATERPROOF MEMBRANES STANDARDS.

Waterproofing material shall comply with the following standards.
AS 3740 and local regulations.

2.1.1 GUARANTEE

The waterproof membrane manufacturer to provide a written guarantee for the whole of the waterproofing work, against failure due to defective material for a period of ten (10) years after the date of final completion.

2.1.2 SURFACE PREPARATION

The surface to be waterproofed must be free of grease, oil, dust and other contaminants.

The surface to be waterproofed must be primed with

Primer & Grout Additive Internally and Primax externally
Made by **Construction Chemicals Pty Ltd.**

2.1.3 All waterproofing to be carried out shall be installed by only and applicator approved by the manufacturer to obtain a ten (10) year product guarantee,

2.1.4 Any deviation from the materials specified in this schedule must be approved by the Architect in writing only.

2.1.5 SCHEDULE INTERNALLY :

Provide and install in all areas to be waterproofed
waterproof membrane manufactured by Construction Chemicals, strictly in accordance with the manufacturers written instructions.

All areas in which the waterproof membrane is installed shall be **water Tested 24 hours** prior to the laying of the bed over the finished membrane. The membrane must be allowed to cure for 72 hours prior to water testing.

-
-

2.1.6 EXTERNALLY.

Provide and install in all external locations **LIQUID FLASH II** waterproof membrane, manufactured by Construction Chemicals, strictly in accordance with the manufacturers written instructions.

-

2.1.7 Waterproof membrane must be allowed to cure for a minimum of 24 hours prior to fixing tiles or a screed bed over the finished membrane.